
GRASS VALLEY SCHOOL DISTRICT

REQUEST FOR PROPOSAL #20-002

CABLING, E-Rate YR 23 (2020-2021)

Addendum 01

2/25/2020

The following notes came about as a result of the site walk on February 19th:

1. Bell Hill Academy:
 - a. Classrooms A1, A2, A3, and A4 do not have drop ceilings so will require raceway to place the drops in the middle of the rooms.
 - b. Office B1 drops will be on the opposite wall of where marked (by the outside door).
 - c. The MDF is full at this point so GVSD will reorganize the UPS setup (currently taking 6RU) to make space needed for new patching.
 - i. The old fiber tray could also be removed and, if possible, the multi-mode fiber moved to the new fiber tray at the top of the cabinet.
2. Grass Valley Charter School:
 - a. GVSD will move the light fixture currently in the middle of the IDF rack in the custodial closet (top of diagram).
3. Lyman Gilmore Middle School:
 - a. The Building C-3 IDF will need to be replaced with a 24" wide by 24" deep by **36" high** cabinet.
 - i. This is opposed to the standard 24" by 24" by 24" cabinet called out in the [Network Infrastructure Cabling System Design, Performance and Installation Standards document](#).
 - b. GVSD will remove some of the cable management in the NOC rack to make space for the additional patch panel required for the requested drops.
 - c. GVSD tech rep will work with the renovation contractors and winning cabling contractor to:
 - i. Determine a plan for walls that stop at drop ceilings (which will be removed and not replaced) and raceways running up those walls, etc.
 - ii. Organize, remove, or replace existing cabling, which is suspected to be mostly laying on drop ceiling tiles.
 - iii. Determine if new cabling, J-hooks, and other infrastructure need be ordered in black.
 1. Note that painting of cables voids the warranty.
 2. Painting contractors to be informed of this regardless of color of equipment installed and held accountable for wrapping cabling prior to painting.
4. Margaret G. Scotten School:
 - a. IDF cabinet in the custodian closet of the Reception office is NOT to be changed.
 - i. Site walk determined a new cabinet would obstruct fire-safety equipment and require extending cables, which may not have sufficient service loops.
 - ii. Alternatively, wire management will be changed from 2RU to 1RU or removed completely to accommodate the new patching.
5. District wide notes:
 - a. Tie wrapping to conduits and pipes is not acceptable.
 - b. All runs must be in conduit or surface-mounted raceway.
 - i. No exposed cables.
 - ii. Exceptions will considered for areas of Gilmore where all infrastructure in ceilings will be exposed when drop ceilings are removed with approval from GVSD technology representative.

- c. GVSD to provide photographs of the current status of IDF and MDF cabinets for proposing vendors to review in a future addendum.
- d. Link to cabling specifications in the RFP was difficult to access. Content can also be found at <https://tinyurl.com/GVSDMasterData-2020>
- e. GVSD is open to having construction take place after hours (starting at or after 4pm) during the school year to be agreed upon with the winning cabling contractor.
 - i. The winning cabling contractor must be willing to work around occasional evening events at all school sites.